

Rick Johnson
Owner/President
Since 1982



Free Estimates
All Work Guaranteed

ESTIMATE

Joe Amato
310 Royal St.
New Orleans, LA 70130

8/6/22

WOOD T&G DECKING

This is an estimate to replace the tongue and groove decking on the balcony as per City drawings. We will use exterior pressure treated five quarter T&G wood deck boards. This is carpentry only and does not include painting. But we will prime the new tongue and groove deck boards. You have to prime all four sides of the deck boards for the warranty from the manufacturer. We will remove and haul off all of the trash and debris. We will install new tongue and groove deck boards. We will install new exterior pressure treated 4x4 runners underneath the deck boards for support and to nail to. We will install a new 1x10 cypress fascia board and a new exterior pressure treated 1 3/4" trim molding on the front of the fascia. The material cost for the wood and the primer is **1,326.74**

The demo and trash haul is **\$920**

The carpentry labor is **\$4,320**

Total cost to replace the balcony with wood is **\$6,866.74**

Please let me know if you have any questions or concerns.
Thank you very much, Rick Johnson